COST ESTIMATES FOR WORK ITEM OF PROJECTS
as of January
Table 10

A. Preventive Maintenance

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		NCR	CAR	REGION I	REGION II	REGION III	REGION IV-A
ASPHALT/ CONCRETE	Overlay 50mm	8,316,218.19	10,794,103.89	9,590,122.52	10,130,132.46	8,369,698.16	8,241,166.48
	Overlay 80mm	13,236,194.48	17,115,107.83	15,222,672.98	16,070,663.61	13,326,529.88	13,091,297.13
	Overlay 100mm	16,297,904.93	21,203,668.75	18,787,687.48	19,837,870.72	16,373,823.18	16,103,635.14
ASPHALT	Overlay 50mm with minor corrections	9,024,093.06	11,528,805.67	10,306,593.84	10,801,360.53	9,047,178.94	8,977,377.69
(Assumption : Half of the existing pavement w/ corrections)	Overlay 80mm with minor corrections	13,944,069.35	17,849,809.61	15,939,144.30	16,741,891.68	14,004,010.67	13,827,508.34
	Overlay 100mm with minor corrections	17,005,779.80	21,938,370.53	19,504,158.80	20,509,098.78	17,051,303.97	16,839,846.36
CONCRETE	Reblocking with overlay 50mm	12,454,713.92	15,744,640.24	14,226,289.94	15,291,274.76	13,008,041.42	12,702,274.73
(Assumption : 30% for reblocking)	Reblocking with overlay 80mm	17,374,690.22	22,065,644.18	19,858,840.41	21,231,805.91	17,964,873.15	17,552,405.38
	Reblocking with overlay 100mm	20,436,400.66	26,154,205.10	23,423,854.90	24,999,013.02	21,012,166.45	20,564,743.40

A. Preventive Maintenance

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		REGION IV-B	REGION V	REGION VI	REGION VII	REGION VIII	REGION IX
ASPHALT/ CONCRETE	Overlay 50mm	12,566,957.59	12,468,117.51	10,411,802.45	10,332,916.12	12,041,398.84	14,163,731.94
	Overlay 80mm	19,981,389.93	19,826,485.72	16,510,442.35	16,392,158.42	19,124,453.01	22,529,802.38
	Overlay 100mm	24,750,749.30	24,552,751.14	20,416,556.82	20,251,678.80	23,681,430.37	27,935,342.55
ASPHALT	Overlay 50mm with minor corrections	13,299,325.35	13,216,565.44	11,099,080.50	11,027,026.16	12,707,393.18	14,903,175.82
(Assumption : Half of the existing pavement w/ corrections)	Overlay 80mm with minor corrections	20,713,757.69	20,574,933.65	17,197,720.40	17,086,268.46	19,790,447.35	23,269,246.25
	Overlay 100mm with minor corrections	25,483,117.06	25,301,199.07	21,103,834.87	20,945,788.84	24,347,424.71	28,674,786.43
CONCRETE	Reblocking with overlay 50mm	18,309,281.33	17,734,206.40	15,365,425.05	16,018,607.22	17,424,509.07	19,722,886.79
(Assumption : 30% for reblocking)	Reblocking with overlay 80mm	25,723,713.67	25,092,574.62	21,464,064.95	22,077,849.52	24,507,563.23	28,088,957.23
	Reblocking with overlay 100mm	30,493,073.04	29,818,840.03	25,370,179.42	25,937,369.91	29,064,540.59	33,494,497.40

A. Preventive Maintenance

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)				
		REGION X	REGION XI	REGION XII	REGION XIII	AVERAGE
ASPHALT/ CONCRETE	Overlay 50mm	11,961,734.61	12,410,988.88	11,645,721.74	16,446,188.91	11,243,187.52
	Overlay 80mm	19,034,453.15	19,688,504.67	18,503,917.38	26,158,658.49	17,863,295.71
	Overlay 100mm	23,559,517.00	24,427,394.69	22,902,261.00	32,455,555.87	22,096,114.23
ASPHALT	Overlay 50mm with minor corrections	12,719,008.03	13,089,429.98	12,356,627.12	17,167,082.36	11,954,382.73
(Assumption : Half of the existing pavement w/ corrections)	Overlay 80mm with minor corrections	19,791,726.57	20,366,945.77	19,214,822.77	26,879,551.94	18,574,490.93
	Overlay 100mm with minor corrections	24,316,790.42	25,105,835.78	23,613,166.39	33,176,449.32	22,807,309.44
CONCRETE	Reblocking with overlay 50mm	17,451,484.98	17,278,719.64	16,504,717.35	22,039,004.19	16,329,754.82
(Assumption : 30% for reblocking)	Reblocking with overlay 80mm	24,524,203.52	24,556,235.43	23,362,912.99	31,751,473.77	22,949,863.01
	Reblocking with overlay 100mm	29,049,267.37	29,295,125.45	27,761,256.61	38,048,371.15	27,182,681.53

B. Rehabilitation/Reconstruction

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		NCR	CAR	REGION I	REGION II	REGION III	REGION IV-A
ASPHALT	Recon AC 50mm	13,143,359.95	17,296,092.94	14,601,570.51	15,912,700.88	14,296,888.98	13,687,888.05
(Assumption : with base failure)	Recon AC 80mm	17,997,296.41	23,468,883.93	20,151,036.19	21,739,942.52	19,150,026.60	18,468,791.15
	Recon AC 100mm	21,002,904.88	27,444,630.15	23,647,696.96	25,418,097.13	22,114,525.45	21,422,278.21
CONCRETE	Reconstruction PCC 230mm	15,885,537.75	17,569,184.11	16,288,646.18	18,363,410.26	16,646,346.11	15,439,865.86
(Assumption : with base failure)	Reconstruction PCC 280mm	18,048,388.76	20,027,432.10	18,522,667.53	20,932,332.32	18,873,239.36	17,636,205.75
	Reconstruction PCC 300mm	18,931,268.24	21,033,363.77	19,433,074.21	21,979,262.34	19,782,210.81	18,530,099.39
ASPHALT	Upgrade to Concrete 230mm	13,119,946.26	15,895,586.56	13,795,345.36	15,852,780.98	14,000,745.23	13,203,997.46
	Upgrade to Concrete 280mm	15,426,646.52	18,686,266.02	16,212,706.92	18,670,299.56	16,451,964.82	15,556,228.80
	Upgrade to Concrete 300mm	16,369,193.46	19,829,402.45	17,199,022.54	19,820,028.25	17,453,753.73	16,514,680.14
CONCRETE	Reblocking 230mm	7,149,685.00	8,547,866.40	8,023,265.39	8,935,040.30	7,991,640.09	7,711,777.80
(Assumption : 50% reblocking)	Reblocking 280mm	8,222,526.88	9,766,411.66	9,129,724.19	10,208,347.12	9,095,130.68	8,800,048.67
	Reblocking 300mm	8,663,702.56	10,268,443.63	9,584,047.32	10,730,691.00	9,549,074.74	9,246,376.68

B. Rehabilitation/Reconstruction

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		REGION IV-B	REGION V	REGION VI	REGION VII	REGION VIII	REGION IX
ASPHALT	Recon AC 50mm	18,822,364.03	19,215,454.94	16,536,666.35	16,538,269.33	18,036,492.61	21,097,609.54
(Assumption : with base failure)	Recon AC 80mm	26,088,769.46	26,432,387.65	22,511,066.68	22,476,590.72	24,990,683.99	29,314,183.00
	Recon AC 100mm	30,745,628.52	31,050,181.74	26,320,270.44	26,241,870.74	29,448,315.83	34,606,223.54
CONCRETE	Reconstruction PCC 230mm	21,808,603.70	18,918,924.72	17,966,018.02	20,554,814.53	19,678,280.97	20,496,394.99
(Assumption : with base failure)	Reconstruction PCC 280mm	24,689,740.92	21,531,203.88	20,358,452.73	23,426,816.17	22,362,295.17	23,275,058.76
	Reconstruction PCC 300mm	25,864,860.52	22,596,735.08	21,332,543.59	24,598,518.75	23,458,440.70	24,406,255.46
ASPHALT	Upgrade to Concrete 230mm	17,567,593.69	16,518,939.43	15,182,183.38	17,494,234.76	16,590,221.51	17,274,903.71
	Upgrade to Concrete 280mm	20,746,279.87	19,441,372.94	17,842,776.95	20,623,229.27	19,546,723.45	20,369,800.99
	Upgrade to Concrete 300mm	22,044,640.24	20,635,046.91	18,927,768.23	21,901,276.66	20,755,602.06	21,631,776.95
CONCRETE	Reblocking 230mm	9,868,534.91	9,071,361.37	8,566,367.48	9,800,726.20	9,288,404.54	9,579,706.29
(Assumption : 50% reblocking)	Reblocking 280mm	11,298,644.90	10,366,310.92	9,751,718.99	11,225,803.14	10,619,738.56	10,957,598.94
	Reblocking 300mm	11,885,264.14	10,897,983.01	10,237,866.76	11,810,615.31	11,166,774.90	11,521,856.40

B. Rehabilitation/Reconstruction

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)				
		REGION X	REGION XI	REGION XII	REGION XIII	AVERAGE
ASPHALT	Recon AC 50mm	18,976,449.80	18,288,392.41	17,761,766.83	23,380,545.01	17,349,532.01
(Assumption : with base failure)	Recon AC 80mm	25,896,829.05	25,447,363.48	24,501,817.02	32,947,164.89	23,848,927.05
	Recon AC 100mm	30,306,142.73	30,093,417.74	28,808,027.46	39,133,056.99	27,987,704.28
CONCRETE	Reconstruction PCC 230mm	20,329,541.56	17,183,854.66	17,669,605.82	20,732,033.98	18,470,691.45
(Assumption : with base failure)	Reconstruction PCC 280mm	23,025,502.53	19,570,325.34	19,998,005.95	23,455,395.96	20,983,316.45
	Reconstruction PCC 300mm	24,125,307.37	20,542,802.31	20,949,490.80	24,564,876.80	22,008,069.38
ASPHALT	Upgrade to Concrete 230mm	17,010,765.38	15,130,255.63	14,806,251.41	17,231,854.77	15,667,225.35
	Upgrade to Concrete 280mm	20,027,919.24	17,781,634.95	17,387,175.76	20,261,111.39	18,439,508.59
	Upgrade to Concrete 300mm	21,260,561.23	18,863,557.04	18,443,132.43	21,497,157.27	19,571,662.47
CONCRETE	Reblocking 230mm	9,429,947.52	8,411,391.47	8,398,264.93	9,683,901.27	8,778,617.56
(Assumption : 50% reblocking)	Reblocking 280mm	10,766,599.24	9,594,021.56	9,551,954.77	11,033,629.28	10,024,263.09
	Reblocking 300mm	11,315,295.77	10,079,416.36	10,026,764.79	11,586,821.31	10,535,687.17

C. Road Upgrading

LEVEL OF IMPROVEMENT	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		FLAT TERRAIN					
		NCR	CAR	REGION I	REGION II	REGION III	REGION IV-A
GRAVEL TO ASPHALT	AC 50mm	12,397,652.52	16,305,385.20	13,685,214.05	15,038,335.49	13,701,131.38	12,704,977.65
	AC 80mm	17,363,341.87	22,688,922.23	19,366,402.62	21,036,010.14	18,713,813.23	17,598,608.45
	AC 100mm	20,440,749.42	26,803,795.14	22,948,265.53	24,825,735.93	21,782,295.35	20,624,368.31
GRAVEL TO CONCRETE	PCC 230mm	15,264,000.85	16,665,850.34	15,278,530.22	17,531,892.78	16,170,638.47	14,267,832.79
	PCC 280mm	17,686,964.75	19,343,432.84	17,735,765.09	20,360,953.87	18,681,336.79	16,646,254.96
	PCC 300mm	18,674,010.83	20,436,750.69	18,735,112.54	21,511,973.08	19,703,997.02	17,612,215.67

LEVEL OF IMPROVEMENT	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		FLAT TERRAIN					
		REGION IV-B	REGION V	REGION VI	REGION VII	REGION VIII	REGION IX
GRAVEL TO ASPHALT	AC 50mm	19,207,347.88	18,428,118.59	15,924,319.79	16,046,277.78	17,663,727.71	20,738,448.92
	AC 80mm	26,697,628.96	25,851,186.61	22,085,189.21	22,167,738.62	24,811,016.04	29,175,137.98
	AC 100mm	31,502,432.92	30,604,812.45	26,016,708.41	26,053,208.25	29,395,741.93	34,612,673.68
GRAVEL TO CONCRETE	PCC 230mm	22,957,504.10	18,312,886.48	17,556,723.84	20,314,584.55	19,635,633.90	20,561,987.11
	PCC 280mm	26,377,923.27	21,213,390.36	20,264,823.28	23,530,474.55	22,683,367.46	23,738,331.23
	PCC 300mm	27,771,639.00	22,394,491.05	21,365,673.22	24,840,604.93	23,926,146.64	25,030,095.78

LEVEL OF IMPROVEMENT	SCOPE OF WORK	UNIT COST/KM. (PESOS)				
		FLAT TERRAIN				
		REGION X	REGION XI	REGION XII	REGION XIII	AVERAGE
GRAVEL TO ASPHALT	AC 50mm	18,703,634.33	17,322,035.11	17,246,023.80	23,033,492.25	16,759,132.65
	AC 80mm	25,848,716.81	24,656,140.34	24,164,440.20	32,816,900.99	23,440,074.64
	AC 100mm	30,406,515.95	29,416,909.57	28,587,675.34	39,146,016.90	27,697,994.07
GRAVEL TO CONCRETE	PCC 230mm	20,531,893.15	16,219,421.21	17,373,785.33	20,816,196.41	18,091,210.10
	PCC 280mm	23,643,862.42	18,827,137.10	20,024,824.22	23,957,100.91	20,919,746.44
	PCC 300mm	24,911,672.52	19,887,701.32	21,106,066.44	25,235,302.78	22,071,465.84

D. Flooded Sections (Raising of Grade and Drainage)

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		NCR	CAR	REGION I	REGION II	REGION III	REGION IV-A
ASPHALT	AC 50mm	44,075,675.15	47,544,321.43	42,112,832.06	46,113,755.15	46,204,502.29	43,208,213.17
(Assumption : raising of grade by 1.00 meter & removal/ replacement of RCPC at both sides)	AC 80mm	49,059,434.95	53,957,013.03	47,814,349.40	52,141,278.28	51,261,998.72	48,115,031.55
	AC 100mm	52,154,991.21	58,098,022.52	51,416,665.29	55,957,803.52	54,367,725.30	51,156,484.87
CONCRETE	PCC 230mm	47,061,377.82	48,093,723.46	43,843,160.22	48,801,442.69	48,960,341.05	44,865,239.68
(Assumption : raising of grade by 1.00 meter & removal/ replacement of RCPC at both sides)	PCC 280mm	49,526,547.66	50,833,353.34	46,348,190.53	51,694,165.41	51,560,713.32	47,279,558.22
	PCC 300mm	50,531,092.26	51,952,157.59	47,367,340.77	52,871,333.88	52,619,967.82	48,260,562.19

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		REGION IV-B	REGION V	REGION VI	REGION VII	REGION VIII	REGION IX
ASPHALT	AC 50mm	61,273,708.31	58,307,392.04	51,485,904.82	55,052,572.43	57,044,285.80	53,094,340.24
(Assumption : raising of grade by 1.00 meter & removal/ replacement of RCPC at both sides)	AC 80mm	68,872,449.67	65,801,570.31	57,705,618.53	61,237,517.94	64,249,321.77	61,576,603.65
	AC 100mm	73,756,005.21	70,609,699.24	61,683,772.34	65,172,163.93	68,878,943.81	67,050,929.28
CONCRETE	PCC 230mm	65,687,321.78	58,634,867.75	53,489,009.19	59,716,583.80	59,375,131.66	53,203,826.27
(Assumption : raising of grade by 1.00 meter & removal/ replacement of RCPC at both sides)	PCC 280mm	69,301,380.54	61,668,250.41	56,310,250.04	63,052,087.84	62,531,876.34	56,468,913.97
	PCC 300mm	70,773,197.66	62,903,204.01	57,457,084.42	64,410,744.40	63,818,901.47	57,796,818.27

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)				
		REGION X	REGION XI	REGION XII	REGION XIII	AVERAGE
ASPHALT	AC 50mm	58,873,225.47	50,653,430.27	54,808,830.89	61,193,709.48	51,940,418.69
(Assumption : raising of grade by 1.00 meter & removal/ replacement of RCPC at both sides)	AC 80mm	66,099,736.58	58,038,846.71	61,792,024.07	71,027,515.87	58,671,894.44
	AC 100mm	70,718,652.28	62,840,993.97	66,265,022.86	77,396,627.94	62,970,281.47
CONCRETE	PCC 230mm	61,204,737.20	49,875,112.08	55,338,639.87	59,291,253.36	53,590,110.49
(Assumption : raising of grade by 1.00 meter & removal/ replacement of RCPC at both sides)	PCC 280mm	64,466,175.81	52,582,878.20	58,110,819.74	62,528,918.98	56,516,505.02
	PCC 300mm	65,794,452.29	53,684,170.27	59,241,175.42	63,846,466.81	57,708,041.85

E. Drainage and Slope Protection

SURFACE TYPE	SCOPE OF WORK	UNIT COST/L.M. (PESOS)					
		NCR	CAR	REGION I	REGION II	REGION III	REGION IV-A
SLOPE PROTECTION (Per Linear Meter)	Grouted Riprap (H=3.00)	6,002.03	5,360.74	5,253.77	5,831.47	5,622.62	5,347.94
	Stone Masonry (H=3.00)	13,642.08	13,084.14	12,591.98	14,000.38	13,214.86	12,793.82
DRAINAGE (Per Linear Meter)	Grouted Line Canal (2.01x0.57), v-shaped	2,431.14	2,253.63	2,165.22	2,375.73	2,323.11	2,248.71
	Concrete Lined Canal (H=1.00x0.60)	8,421.01	8,659.18	7,848.40	8,648.54	8,020.45	7,937.14
	RCPC (910mm. Dia.)/Manhole	11,699.72	10,781.54	9,852.04	10,582.87	10,410.89	11,328.75

SURFACE TYPE	SCOPE OF WORK	UNIT COST/L.M. (PESOS)					
		REGION IV-B	REGION V	REGION VI	REGION VII	REGION VIII	REGION IX
SLOPE PROTECTION (Per Linear Meter)	Grouted Riprap (H=3.00)	6,302.91	5,934.72	6,475.30	6,914.37	6,012.69	6,613.56
	Stone Masonry (H=3.00)	15,216.80	14,270.15	14,903.15	16,296.83	14,409.64	15,813.29
DRAINAGE (Per Linear Meter)	Grouted Line Canal (2.01x0.57), v-shaped	2,481.80	2,418.72	2,610.01	2,688.54	2,559.58	2,667.39
	Concrete Lined Canal (H=1.00x0.60)	8,992.45	8,982.16	8,206.71	9,207.31	9,456.39	8,748.07
	RCPC (910mm. Dia.)/Manhole	11,610.79	12,562.59	11,069.40	12,601.64	13,200.94	10,360.49

SURFACE TYPE	SCOPE OF WORK	UNIT COST/L.M. (PESOS)				
		REGION X	REGION XI	REGION XII	REGION XIII	AVERAGE
SLOPE PROTECTION (Per Linear Meter)	Grouted Riprap (H=3.00)	6,620.34	5,769.03	6,706.58	5,836.71	6,037.80
	Stone Masonry (H=3.00)	15,809.38	13,679.07	15,473.78	14,235.75	14,339.69
DRAINAGE (Per Linear Meter)	Grouted Line Canal (2.01x0.57), v-shaped	2,727.99	2,398.20	2,594.33	2,411.02	2,459.70
	Concrete Lined Canal (H=1.00x0.60)	9,002.20	8,112.61	8,214.63	8,828.78	8,580.38
	RCPC (910mm. Dia.)/Manhole	12,124.30	10,477.06	11,891.74	12,930.95	11,467.86

New Road Construction

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		NCR	CAR	REGION I	REGION II	REGION III	REGION IV-A
CONCRETE	PCC 230mm	21,041,520.95	23,514,096.53	21,391,116.64	24,894,698.85	25,777,891.87	19,350,209.94
	PCC 230mm, w/ slope protection	29,406,963.42	30,556,408.59	28,715,899.78	32,490,186.77	31,963,065.80	27,380,977.90
ASPHALT	AC 50mm	20,599,699.61	25,271,513.81	21,938,596.45	24,884,560.11	25,990,111.49	19,548,766.21
	AC 50mm, w/ slope protection	29,171,603.42	32,518,582.18	29,462,507.36	32,689,690.22	32,369,246.51	27,786,428.98

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)					
		REGION IV-B	REGION V	REGION VI	REGION VII	REGION VIII	REGION IX
CONCRETE	PCC 230mm	41,439,129.01	31,155,367.74	29,062,470.11	32,397,451.47	30,834,909.60	30,156,170.57
	PCC 230mm, w/ slope protection	44,627,097.92	36,405,144.86	35,672,154.67	39,709,613.99	36,974,501.39	37,732,393.65
ASPHALT	AC 50mm	42,677,086.66	34,037,901.80	30,419,203.36	31,370,819.91	32,271,613.40	34,045,371.19
	AC 50mm, w/ slope protection	46,024,184.88	39,472,937.30	37,231,575.54	38,890,899.90	38,600,929.09	41,832,472.73

SURFACE TYPE	SCOPE OF WORK	UNIT COST/KM. (PESOS)				
		REGION X	REGION XI	REGION XII	REGION XIII	AVERAGE
CONCRETE	PCC 230mm	35,074,734.41	26,346,055.80	29,473,421.30	31,155,890.40	28,316,570.95
	PCC 230mm, w/ slope protection	40,554,187.98	32,722,040.19	36,218,981.46	37,225,547.49	34,897,197.87
ASPHALT	AC 50mm	37,146,402.32	29,597,271.80	32,395,470.51	37,272,301.78	29,966,668.15
	AC 50mm, w/ slope protection	42,815,069.69	36,170,949.10	39,338,968.63	43,532,696.98	36,744,296.41

Note :

1. The price of construction materials are based on the regional average prices (4th Quarter 2022 or latest CMPD value) plus 15% mark-up for the hauling cost, calculated equipment rates are based on the operated dry rates from the latest ACEL Rates (26th Edition) incorporated with fuel/diesel and lubricant requirement per equipment, and labor rates are based on regional labor average (December 2022) in accordance with DO No. 63 S. 2022 - Guidelines in Addressing the Effect of the Increasing Prices of Construction Materials and Equipment Rental Rates Utilized for Infrastructure Projects

2. Item A to C, the Estimated Cost excludes cost for Drainage and Slope Protection Works.

3. The Estimated Cost was assumed for a flat terrain condition and specific scope of works for funding purposes. A cost factor of 10% for rolling mountainous terrain condition may be applied.

Notes:

1.) *Road data provided are as of 14 October 2022.*

2.) *The unit of measure for Road Data is* ***kilometers****.*

3.) *National Roads are classified into:*

Primary Roads *- A contiguous length of significant road sections extending linearly without any breaks or forks that connect major cities (At least around 100,000 population) comprising the main trunk line or the backbone of the National Road System.*

Secondary Roads *- Directly connect cities to national primary roads (except in metropolitan areas) or those not included in the category of major cities. Likewise, said roads directly connect major ports, major ferry terminals, major airports, tourist service centers, major government infrastructure to national primary roads. They also directly connect provincial capitals within the same region.*

Tertiary Roads *- Other existing roads under DPWH which perform a local function. (In the map, these roads are represented only by letters.)*

4.) No Assessment *refers to Road Sections that are either under construction and/or segments with length below the 50-meter gauging length.*

For questions regarding this website contact feedback@dpwh.gov.ph